



15-167-20513-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duane Rankin of Sage Drilling Co., INC. has this date requested permission to plug the following described well:

Mr. Will P. Ash guarantees payment of the plugging fee.

Operator's full Name: Will P. Ash

Complete Address: 230 Sutton Place, Wichita, Kansas

Lease Name: Beisel Well No. # 3

Location: App. NE NW ^{NW} Sec. 25 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 2869 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Duane Rankin was instructed to plug the well as follows:

8 5/8" csg. 262' Cwc.

Circulated hole with heavy mud to 480', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 250' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement

with Sun Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Luman
Conservation Division Agent