

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-01599-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 26 Twp. 13S Rge. 20W (XXXXXX)

NORTH

			X
	26		

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Imperial Drilling Company, Inc.
Lease Name Herman "C" Well No. 1
Office Address 903 Union Natl. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 8 1952
Application for plugging filed November 8 1952
Application for plugging approved November 8 1952
Plugging commenced November 8 1952
Plugging completed November 8 1952
Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3832 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud 200 feet.
Set #1 plug with 15 sacks cement.
Set #2 plug 40 feet down from top of hole with 10 sacks cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1952
11-14-52
CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Drilling Company, Inc.
Address 903 Union National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

RAYMOND L. BACON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL DRILLING COMPANY, INC.

(Signature) BY: Raymond L. Bacon VICE-Pres
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November, 1952

My commission expires 7-54

24-2675-S 2-52-20M

PLUGGING
FILE SEC 26 13R 204
BOOK PAGE 58 LINE 22



DRILLER'S LOG

15051-01599-00-00

Imperial Drilling Company, Inc.
903 Union National Bank Bldg.
Wichita 2, Kansas

Herman "C" #1
NE NE NE
26-13S-20W
Ellis County, Kansas

Total Depth: 3832'

Elevation: 2132 R.B.
Production: D & A

Commenced: 10-27-52

Completed: 11-8-52

Contractor: Imperial Drilling Co., Inc.
Wichita, Kansas

Casing Record: Set 218' of 8 5/8" surface pipe w/150 sacks cement.

Figures indicate bottom of formations:

Shale & Sand	60'			
Surface sand & Clay	218'			
Surface Clay & Sand	500'		<u>TOPS</u>	
Shale & Shells	1000'			
Dakota	1200'	Anhydrite	1440'	+ 692
Shale, Shells & Red Bed	1245'	Heebner	3388'	-1256
Red Bed	1440'	Lansing	3428'	-1296
Anhydrite	1465'	Base K. C.	3778'	-1646
Lime & Shale	1735'	Cong. (Est.)	3791'	
Shale & Shells	2160'	Arbuckle	3802'	-1670
Lime	2165'			
Shale & Lime	3420'	T. D.	3832'	-1700
Lime	3832'			
Total Depth	3832'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond L. Bacon
Raymond L. Bacon

Subscribed and sworn to before me this 11th day of November, 1952.

Marquitta Little
Notary Public

My commission expires: 1-4-58

PLUGGING
WELL SEC. 26 T. 13 R. 20
BOOK PAGE 58 LINE 22

STATE OF KANSAS
NOV 11 1952
CONSERVATION
Wichita