

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

15.009.07520.00.00

OPERATOR: License #: 7383
Name: Grady Bolding Corporation
Address 1: P.O. Box 486
Address 2: _____
City: Ellinwood State: KS Zip: 67526 + 0486
Contact Person: Grady Bolding
Phone: (620) 564-2240
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - Drilled 1949
Spot Description: NE SW NE
_____ Sec. 34 Twp. 20 S. R. 12 East West
3,630 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Langrehr Well #: 3
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 6-23-11
Plugging Completed: 6-24-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	265'	None
			5-1/2"	3392'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated casing @1500' and 650'. Ran 2-3/8" tubing to 3200', pumped 11 sxs. gel, 75 sxs. cement and 200# hulls, pulled tubing up to 1500'. pumped 100 sxs. cement & 100# hulls, pulled up to 680', pumped 20 sacks cement and circulated to surface. Topped off with 20 sacks cement. Used 60/40 pos, 4% gel. Plugging Complete.

RECEIVED
JUL 15 2011

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2945

KCC WICHITA

Name of Party Responsible for Plugging Fees: Grady Bolding Corporation
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Mike Kelso