

15-071-20258-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Greely SEC. 32 TWP. 18 RGE. 39 E/W
 Location as in quarters or footage from lines:
C - NE NE NE

Lease Owner Westburn Oil Co.
 Lease Name Cokes Well No. 1-32
 Office Address 308 One Denver Place, Denver, Co. 80202
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 10-27-1983
 Plugging completed 10-31-1983
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Non Commercial Value
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi
 Producing formation Hugoton Depth to top 2922' bottom 2926' T.D. 3247'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	312'	0'
Production				4 1/2"	3247'	2515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 1 sk. hulla & 20 sks. cement to 2740' & pressured to 750 lbs.
Shot pipe @ 2515' & pumped 50 sks. cement 2515' to 2365'
Layed down 4 1/2" to 1900' & pumped 40 sks. cement 1900' to 1780'
Layed down 4 1/2" to 360' & pumped 50 sks. cement 360' to 210'
Put bridge & 10 sks. cement 40' to 0'
Cut off 8 5/8", 3 1/2' below ground level & weld plate on same

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1983
 11-21-83
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
 Lic. # 6497

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
 Box F, Sublette, Ks. 67877
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of Nov., 19 83

Sandra L. Eves
 Notary Public.

My Commission expires: 12-6-84

SONDRA L. EVES
 Haskell County, Ks.
 My Appt. Exp. 12-6-84

SONDRA L. EVES
 Haskell County, Ks.
 My Appt. Exp.