

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Greeley County. Sec. 5 Twp. 18 Rge. 40 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

Lease Owner Smith Cattle Inc.  
Lease Name Smith Cattle Well No. 9  
Office Address Tribune, Kansas 67879  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 6-5 1981  
Application for plugging filed 6-5 1981  
Application for plugging approved 6-5 1981  
Plugging commenced 6-5 1981  
Plugging completed 6-5 1981

Reason for abandonment of well or producing formation Structure running too low for production  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2660  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	294'	Left

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spot 50 Sx. @ 720'  
Spot 50 Sx. @ 270'  
10 Sx. 40' to 0  
5 Sx. Rathole

By Halliburton

RECEIVED  
STATE CORPORATION COMMISSION  
8-19-81  
AUG 19 1981

(If additional description is necessary, use BACK of CONSERVATION DIVISION sheet)

Name of Plugging Contractor Lakin Drilling Co. Wichita, Kansas

STATE OF Kansas COUNTY OF Greeley, ss. \_\_\_\_\_  
(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Ed Smith - Vice Pres  
Box 399 Tribune, Kansas 67879  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of Aug., 1981



Wayne D. Stephen  
Notary Public.

My commission expires \_\_\_\_\_

OPERATOR: Smith Cattle Co.  
 CONTRACTOR: Lakin Drilling Co.  
 WELL NAME: Smith Cattle # 9  
 LOCATION: 5-18-40  
Greeley County, Kansas  
 GEOLOGIST: \_\_\_\_\_  
 SPUD DATE: 6-2-81  
 COMPLETION DATE: 6-5-81

FOOTAGE:		
<u>0</u>	<u>200</u>	<u>Clay &amp; Sand</u>
<u>200</u>	<u>294</u>	<u>Shale</u>
<u>294</u>	<u>1452</u>	<u>Shale</u>
<u>1452</u>	<u>1968</u>	<u>Shale &amp; Anhy</u>
<u>1968</u>	<u>2336</u>	<u>Salt</u>
<u>2336</u>	<u>2626</u>	<u>Shale &amp; Salt</u>
<u>2626</u>	<u>2650</u>	<u>Anhy</u>
<u>2650</u>	<u>2660</u>	<u>Shale</u>
_____	<u>2660</u>	<u>T.D.</u>
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

REPORT: Spud in @ 4:30 P.M. 6-2-81 12 1/4" Hole to 294'  
Run 8 Jts. 8 5/8" 23# Csg. 285' Set @ 293' Cement with 225  
"H" 3/8 c.c. Plug down @ 9:30 P.M. 6-2-81 by Howco  
 \_\_\_\_\_  
Plugged & Abandoned @ 2660'  
 \_\_\_\_\_  
50 Sx. @ 720'  
50 sx. @ 270'  
10 Sx. @ 40' to 0  
Completed by Howco @ 6:00 P.M. 6-5-81

\*\*\*\*\*


State of Kansas County of Kearny

Louis C Blankenship, Drilling Supt for Lakin Drilling Co, does hereby state that the above and foregoing is a true and correct copy of the log of the Smith Cattle # 9 lease; 5-18-40 (legal); Greeley (county); Kansas.

LAKIN DRILLING COMPANY

By: [Signature]  
 Louis C Blankenship, Drilling Supt.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 10th day of June, 19 81.



[Signature]  
 Notary Public

My Commission Expires: 6-15-81

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 21 1981

CONSERVATION DIVISION  
 Wichita, Kansas