

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-071-00031-0000

Form CP-4

WELL PLUGGING RECORD

Greeley County, Sec. 14 Twp. 18N Rge. (E) 40 (W)

Location as "NE/CNW/SW" or footage from lines C-SE, SE

Lease Owner PELICAN PRODUCTION CORPORATION

Lease Name WEAVER

Well No. 1

Office Address 602 Queen & Crescent Bldg., New Orleans 12, La.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 4 19 63

Application for plugging filed W. L. Nichols June 4 19 63

Application for plugging approved June 5 19 63

Plugging commenced June 5 19 63

Plugging completed June 5 19 63

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols Moreland, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 5,226 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| NONE      |         |      |    | 13"  | 355    | None       |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed 20 sacks Portland cement ahead of Halliburton plug with drill pipe to a depth of 600 ft. Pushed 30 sacks Portland cement ahead of Halliburton plug with drill pipe to a depth of 350 ft.

Placed Halliburton bottom plug at 25 ft. and dumped 15 sacks Portland cement on top. (Filled to surface)

Cut off 13" surface casing 24" below ground level.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1963  
6-21-63  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Co  
Address 535 Petroleum Bldg., Wichita 2, Kansas

STATE OF Louisiana Parish Orleans  
J. L. Keefe (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. L. Keefe, Vice President  
602 Queen & Crescent Bldg., New Orleans, La  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1963

My commission expires for life.

Notary Public.

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

15-071-00031-0000

COMPANY *Pelican Production Company*

SEC. 14 T. 18S R. 40W  
LOC. C SE SE

FARM *Weaver*

NO. 1

TOTAL DEPTH *5226'*

COMM. *4/25/63*

COMP. *6/5/63*


COUNTY *Greeley*

KANSAS

SHOT OR TREATED

CONTRACTOR *National Drilling Co., Inc.*

ISSUED



CASING *X*

20 10  
15 8  
12 6  
13 *X* 5

GL 3562

ELEVATION DF 3564

KB 3567

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

*Clay & Sand*

*Sandy Shale*

*Shale*

*Shale*

*Shale & Shells*

*Shale & Lime Shells*

*Shale & Lime Red Bed*

*Shale & Lime*

*Lime & Shale*

*Lime*

*Lime & Shale*

*Lime*

*Shale & Sand*

*Lime Shale & Sand*

*Shale & Lime*

*Lime & Shale*

*Lime & Sand*

*Lime*

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION  
Wichita, Kansas

40  
130  
360  
545  
1375  
1620  
2160  
2970  
~~XXX~~ 3437  
3475  
3560  
4965  
5065  
5114  
5179  
5193  
5203  
5226 TD

*I hereby certify that this a true and correct log of the above described well as shown by the drilling reports.*

*Glen N. Rupe*  
Glen N. Rupe, Vice-President

State of Kansas  
County of Sedgwick

*Subscribed and sworn to before me in and for said county and state this 21st day of June 1963.*

*Marilyn F. Grove*  
Marilyn F. Grove, Notary  
Public

*My commission expires:*  
*July 5, 1966*

