

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15:07/20/139.0000

API NUMBER 6-27-77

LEASE NAME Vogt

WELL NUMBER 1

330 Ft. from N Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 18S RGE. 40E (E) or (W)

COUNTY Greely

Date Well Completed _____

Plugging Commenced 6-3-91

Plugging Completed 6-5-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brock Resources, Inc.

ADDRESS 25th Vine St. Dean Ellner Bldg. Suite 2 Hays, Ks 67601

PHONE# (316) 628-1909 OPERATORS LICENSE NO. 3691

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Goodnow

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Group Depth to Top 2866 Bottom 2909 T.D. 3051

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
<u>Chase Group</u>	<u>Gas</u>	<u>2866</u>	<u>2909</u>	<u>8 5/8</u>	<u>1260</u>	<u>0</u>
				<u>4 1/2</u>	<u>3050</u>	<u>2050</u>

7-8-91
III 08199
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 20 sks. of cement & 1 sk. of hulls from 2909 to 2700

Pump 50 sks. of cement from 1270 to 1170

Pump 50 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.


Ted E. Luebbers

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted E. Luebbers

(Address) _____

SUBSCRIBED AND SWORN TO before me this 5 day of July, 1991



C.C. Schumacher
Notary Public