

LEASE NAME Vogt A

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

C-NE-NE Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 18S RGE. 40W (E) or (W)

COUNTY Greely

LEASE OPERATOR Brock Resources, Inc.

ADDRESS 25th. & Vine St. Dean Ellner Bldg Suite 2 Hays, Ks.

67601

PHONE (316) 628-1909 OPERATORS LICENSE NO. 3691

Date Well Completed

Character of Well Gas

Plugging Commenced 6-5-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-12-91

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Goodrow

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Chase Group Depth to Top 2935 Bottom 2965 T.D. 3050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
<u>Chase Group</u>	<u>Gas</u>	<u>2935</u>	<u>65</u>	<u>8 5/8</u>	<u>1720</u>	<u>0</u>
				<u>4 1/2</u>	<u>3049</u>	<u>1905</u>

III 08 1991
 7-8-91
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 1 sk. of hulls from 2965 to 2750

Pump 50 sks. of cement from 1730 to 1630

Pump 50 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' ft below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547


Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

Ted C. Luebbers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted C. Luebbers

(Address)



SUBSCRIBED AND SWORN TO before me this 5 day of July, 19 91

C.C. Schumacher
 Notary Public

My Commission Expires: 4-15-92

FINAL PRINT

Schlumberger

DUAL BURST THERMAL DECAY TIME LOG

COUNTY GRIEELY	FIELD C-NE-NE	LOCATION VOGT #1-A	WELL BROCK RESOURCES	COMPANY BROCK RESOURCES				RECEIVED STATE CORPORATION COMMISSION MAY 15 1991	
				WELL VOGT #1-A				CONSERVATION DIVISION WICHITA, KANSAS	
COUNTY GRIEELY	FIELD C-NE-NE	LOCATION VOGT #1-A	WELL BROCK RESOURCES	FIELD VOGT #1-A				STATE KANSAS	
				COUNTY GRIEELY				STATE KANSAS	
LOCATION C-NE-NE				Other Services: CYBERSCAN					
API SERIAL NO.		SECT. 16	TWP. 18S	RANGE 40W					
Permanent Datum				GROUND LEVEL		Elev.		Elev.: K.B.	
Log Measured From				K.B.		5.0 F		above Perm. Datum	
Drilling Measured From				K.B.				D.F. G.L.	
Date	12-JAN-1991								
Run No.	2								
Depth Driller	3030.0 F								
Depth Logger (Schl.)	3015.0 F								
Bot. Log Interval	3008.0 F								
Top Log Interval	2500.0 F								
Type Fluid in Hole	WATER								
Salinity NaCl									
Density	8.40 LB/G								
Fluid Level	2200.0 F								
Max. Rec. Temp.									
Deviation									
Logger on Bottom	12-00,1-12								
Equip.	Location	8315		LIBERAL, KANSAS					
Recorded By	KEVIN AIRTH								
Witnessed By	MR. TED LUEBBERS								
BOREHOLE RECORD									
BH Size	7 7/8"								
Depth	3030.0 F								
CASING & TUBING RECORD									
Size	4 1/2"								
Weight	10.5000 LB/F								
Casing Top-Driller									
Casing Top-Logger									
Casing Shoe-Driller	3030.0 F								
Casing Shoe-Logger									

GREAT GUNS

Digital Log

CEMENT BOND-VIL
GAMMA RAY LOG

15-071-20520.0000

COMPANY: BROCK RESOURCES
WELL: VOGT # 1-A
FIELD:
COUNTY: GRIEELY
STATE: KANSAS

FILE NO.:
COUNTRY: U.S.A.

LOCATION: C OF NE NE
SEC: 16 TWP: 18S RGE: 40W

PERMANENT DATUM:	GL	ELEVATIONS:	
DRILLING MEASURED FROM:	KB	KB:	.0
LOG MEASURED FROM:	KB	DF:	.0
ABOVE PERMANENT DATUM:	5.0	GL:	.0

DATE: 19 SEP 90
RUN NO.: 1

BIT SIZE: 7.875

DEPTH--DRILLER: .0
DEPTH--LOGGER: 3024.0
DEPTH TO PLUG: 3029.0
BOTTOM LOG INTERVAL: 3016.0
TOP LOG INTERVAL: 1850.0

SERVICES:
GRCLRECEIVED
STATE CORPORATION COMMISSION

MAY 15 1991

CONSERVATION DIVISION
Wichita, Kansas

UNIT NO.: 58
LOCATION: LIBERAL
WITNESS: MR. TED LUEBBERS
RECORDED BY: R. CAMPBELL

OTHER SERVICES:

SOFTWARE VERSION:

114

The well name, location and borehole reference data were furnished by the customer.