

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-071-206830000

LEASE NAME Elton Russell

WELL NUMBER 1

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 16 TWP. 18S RGE. 40 (E) or (W)

COUNTY Greeley

Date Well Completed 12/01/97

Plugging Commenced 7/15/03

Plugging Completed 7/15/03

LEASE OPERATOR Flex Systems, Inc.

ADDRESS c/o Rob Williams, Agent P.O. Box 15163, Amarillo, TX 79105

PHONE# (806) 374-4555 OPERATORS LICENSE NO. 32199

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 17, 2003 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? Log was attached to CP-1

Producing Formation None Depth to Top          Bottom          T.O. 3009

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase 2911-2948	Water	0	264	8-5/8	264	0
		0	2995	4-1/2	2995	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set

Pumped down 4-1/2" casing: 300# cotton seed hulls & 175 sacks 60/40 Poz, 6% gel, pressured up to 800#. Pumped down 8-5/8"/4-1/2" annulus: 20 sacks 60/40 Poz, 6% gel, pressured up to 500#.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness City, KS 67560


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rob Williams, Agent, P.O. Box 15163, Amarillo, TX 79105

STATE OF TEXAS COUNTY OF POTTER, ss.

Rob Williams, Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rob Williams

(Address) P.O. Box 15163, Amarillo, TX 79105



AND SWORN TO before me this 16 day of July, 2003.

Linda K. McKean  
Notary Public

My Commission Expires: 10-30-2003

JOB LOG

SWIFT Services, Inc.

DATE 7-16-03 PAGE NO. 1

CUSTOMER FLEX SYSTEMS 221  
C/O BOB WILLIAMS 22121  
WELL NO. 21 LEASE SITON PUSSE JOB TYPE PTA TICKET NO. 5675

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1020							ON LOCATION
								4 1/2" @ 2995' PITS = 2911-42
								8 1/2" @ 264'
	1050	5	0		✓			START COMBAT W/ 300" HALLS
	1105		53				800	MAKING 175 SPS AC UP
							600	ENTR 22
	1110		6		✓		500	MAX 70 SPS NOW REACHING AC UP
								WASH UP
	1200							JOB COMPLETE
								THANK YOU
								WALK AWAY SLOW

RECEIVED  
JUL 18 2003  
KCC WICHITA