



15-051-21342-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Cotton of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cotton guarantees payment of the plugging fee.

Operator's full Name: Euwer Petroleum Co. & Parrish Oil Co.

Complete Address: Suite 206 Litwin Bldg., 110 N. Market., Wichita, Ks.

Lease Name: Werth Well No. 1

Location: SW NE NW Sec. 15 Twp. 14 Rge. (E)(W) 16

County: Ellis Total Depth 3466' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Millard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo [Signature]  
Conservation Division Agent