



15-051-20722-05-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Drlg. has this
date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Box 370 Hays, Kansas 67601

Lease Name: Polcyn Well No. 1

Location: A/6 SW SE NE Sec. 10 Twp. 14 Rge. (E)(W) 16

County: Ellis Total Depth 3439' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1000' and displace
25 sk cmt thru drill pipe. Heavy mud to 500' set cementing plug and
displace 50 sk cmt thru drill pipe. Heavy mud to 180' set cementing
plug and displace 25 sk cmt thru drill pipe. Heavy mud to 40' set
cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Masser
Conservation Division Agent