

State of Kansas



FORM CP-2

15-051-22621-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Jerry Helberg of Helberg Oil Company has this date requested permission to plug the following described well:

Operator's Full Name: Knight Oil Company

Complete Address: Box 335, Victoria, Kansas 67671

Lease Name: Dreiling Well No. #1

Location: E/2-SE-SE Sec. 6 Twp. 14 Rge. 16 (E) (W)

County: Ellis Total Depth: 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Jerry Helberg was instructed to plug the well as follows:

8 5/8"-204' sp. cuc. w/125 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem-with heavy mud between all plugs.

1st plug @ 780' with 70 sacks cement

2nd plug @ 210' with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement.

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 29 1981
09-29-81
CONSERVATION DIVISION
Wichita, Kansas

Richard G. Schubert
Conservation Division Agent