

State of Kansas



15-167-19391-00-00

FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COM
DEC 29 1964
12-29-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Walter Well No. # 2

Location: SW SW SW Sec. 14 Twp. 14 Rge. 12 (E) (W) W

County Russell Total Depth 3230 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrell Kelso was instructed to plug the well as follows:

8 5/8" 213' Cwc.

Sanded hole back to 3200' & dumped 4 sax cement with dump bailer. Pulled pipe to 300'; circulated hole with mud; displaced 25 sax cement thru pipe @ 200' with mud pump.

Pulled remaining pipe; set rock bridge @ 40' & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,
[Signature]
Conservation Division Agent