



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 27 1964

02-27-1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Elmer Zimmerman of Woodman & Iannitti Drlg. has this date requested permission to plug the following described well:

Mr. Richard A. Shelly guarantees payment of the plugging fee.

Operator's full Name: Shelly-Miller Drilling, Inc.

Complete Address: 205 Miller Bldg., Wichita, Kansas

Lease Name: Walters Well No. # 4

Location: SW NW SW Sec. 14 Twp. 14 Rge. 12 (E) (W) W

County Russell Total Depth 3247 Oil Well

Gas Well  Input Well  SWD-Well  D & A X Lost Hole

Mr. Elmer Zimmerman was instructed to plug the well as follows:

8 5/8" 209' Gwc.

Filled hole with heavy mud to 200'; set plug with 1/4  
sax hulls; displaced 25 sax cement thru drill pipe. Mud  
to 40'; 1/2 sax hulls; plug & 12 sax cement, cementing  
to base of cellar.

Very truly yours,

D. J. [Signature]  
 Conservation Division Agent