



15-1107-201015-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1973

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

08-29-1973

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling, Inc. has this date requested permission to plug the following described well:

Mr. F. W. Vishnefske guarantees payment of the plugging fee.

Operator's full Name: Saline Basin Petroleum Company

Complete Address: 119 South Santa Fe, Salina, Kansas

Lease Name: R. Herber Well No. # 2

Location: SE SW SW Sec. 13 Twp. 14 Rge. 12 (E)(W)W

County: Russell Total Depth 3259 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" csg. 258' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. Linn
Conservation Division Agent