



15-167-20592-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
04-20-1973
APR 20 1973

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company has this
date requested permission to plug the following described well:

Mr. E. W. Vishnefske guarantees payment of the plugging fee.

Operator's full Name: E. W. Vishnefske/Saline Basin Pet. Company

Complete Address: 119 S. Santa Fe, Salina, Kansas 67401

Lease Name: Ben Major Well No. # 1

Location: NW SE NW Sec. 13 Twp. 14 Rge. 12 (E)(W) W

County: Russell Total Depth 3255 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" csg. 290' Cwc.

Circulated hole with heavy mud to 420', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. Luman
Conservation Division Agent