

6 060249

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-20542-00-07
NW _____, SEC. 18, T. 14 S, R. 11 (W/E)
2310 feet from N/S section line
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Stoppel Well # 1-18

Operator: Kelso Casing Pulling

County Russell

Name & Address Box 176

Well Total Depth 3200 ^{104.00} feet

Chase, Ks. 67542

Conductor Pipe: Size 0 feet

Surface Casing: Size 8^{5/8} feet 551

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address samesas above

Company to plug at: Hour: 9 AM Day: 5 - Month: June Year: 19 84

Plugging proposal received from Millard Kelco

(company name) Kelso Casing Pulling (phone) (316)938-2457

were: Ordered 165 sks 50/50 pozmix 6% gel 3% cal. cl., 15 sks gel, 5 sks hulls and
8^{5/8} plug.

Plugging Proposal Received by *[Signature]*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 5 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 8^{5/8}" set @ 551' w/290 sks 4^{1/2}" set @ 2370' w/250 sks Top perf. @
2154' Plugged bottom w/4 sks cement, sand & 4 sks cement to 2100' Shot pipe 4 time &
recovered 1366'/ Pumped in 8^{5/8}". 4 sks hulls, 25 sks cement, 12 sks gel, 40 sks cmt.
3 sks gel, 1 sk hulls, released plug & followed w/100 sks cmt. w/500 pounds pressure.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1984

Remarks: (If additional description is necessary, use BACK of this form.)

DATE (did / did not) observe this plugging. ⁶⁻²¹⁻⁸⁴

CONSERVATION DIVISION
Wichita, Kansas

Signed *[Signature]*
(TECHNICIAN)

INV. NO. 2101

6-5