

4-010376

9-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-21,559 -00-00

S2 NW NW /4 SEC. 11, 14 S, 11 W
4290 feet from S section line
4620 feet from E section line

Operator license# 32185

Lease: Pasek Well# 2

Operator: J.A.M., Inc.

County: Russell 97.76

Address: 740 Main Street
Russell, Kansas 67665

Well total depth 3008 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well Gas well X, Input well, SWD, D & A

Plugging contractor: J.A.M., Inc. License# 32185

Address: 740 Main Street - Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 29 Month: September Year: 1998

Plugging proposal received from: Tim Mahoney

Company: J.A.M., Inc. Phone: -

Were: Same as below.

10-01-98

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 1 1998

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 29, Month: September, Year: 1998

Actual plugging report: Tied onto 5 1/2" and pumped 40 sxs 60/40 pozmix - 10% gel cement with 500# hulls, followed by 9 sxs of gel and 75 sxs cement. Max. P.S.I. 700#. S.I.P. 200#. 5 1/2" casing set in spider. Could not access backside. Cement was present around head and 5 1/2" appeared solid. Will check backside after head is cut off.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Car Morn
(agent)

INVOICED

VD

Form CP-2/3

DATE 10-2-98
TEL. NO. 51408

JAN 29 1999 9-29