

6 060267

167-21325-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE, SEC. 8, T. 14 S, R. 11 W/E

1320 feet from N/S section line

660 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Esther Pughly Well # 1-8

Operator: Helso Lasing Pulling

County Russell

Name & Address: Box 176, Chase, KS

Well Total Depth 2350 76.38 feet

67524

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 318'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Helso Lasing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 11:00 AM Day: 25 Month: June Year: 19 84

Plugging proposal received from Millard Helso

(company name) Helso Lasing Pulling (phone) 316-938-2457

were: Order 165 lbs. 50 gr. mix - 6 7/8" Gel - 3 3/4" U., 15 lbs. Gel., 5 lbs. Bulls & 8 5/8" plug.

RECEIVED
STATE CORPORATION COMMISSION

JUL 02 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by *Arthur G. Schub* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 PM Day: 25 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - 318' w/ 180 lbs. 4 1/2" set at 2338' w/ 150 lbs.

Top perf at 2125'. Shot pipe 2 times & recovered 1521'. Pumped Bottom w/ 35 lbs. to 1900'. Pumped in 8 5/8" - 4 lbs. bulls, 25 lbs. cement, 12 lbs. Gel., 40 lbs. cement, 3 lbs. Gel., 1 lb. bulls, released plug & followed w/ 100 lbs. cement w/ 700 pounds pressure.

Remarks: By Allied Cementing
(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

INVOICED

Signed *Arthur G. Schub* (TECHNICIAN)

DATE 7-12-84

INV. NO. 2419

June 29th 20