

6 062074

2-5

167-21,338-00-00

API NUMBER 15-

NE, SEC. 7, T. 14 S, R. 11 W/E

4290 feet from S section line

330 feet from E section line

Lease Name Paul B. Biesel Well # 1-7

County Russell 76.70

Well Total Depth 2360 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 301

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5070

Operator: Davies and Company Inc.

Name & Address 2653 So. Birmingham

Tdlsa, Ok. 74114

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Gressel Corporation License Number 5822

Address 1103 So. St. John, Lyons, Ks. 67554

Company to plug at: Hour: 10:30AM Day: 5 Month: Feb Year: 19 90

Plugging proposal received from Mr. Gressel

(company name) Gressel Crop (phone) 316-257-5570

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:15Pm Day: 5 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 301' w/180 sks. 4 1/2" set at 2355' w/175 sks.

Top perf at 2183'. Plugged bottom w/sand and 4 sks cement to 2150'. Shot pipe one time and recovered 1585'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/1200 psi.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: By Allied. Ran line to 1000'. 02-14-90

(If additional description is necessary, use BACK of this form.)

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed Gilbert G. Scheck (TECHNICIAN)

DATE 2-15-90

INV. NO. 27449