

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23180-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 6-14S-11W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: BETTS Well Number: 1
County: RUSSELL Total Vertical Depth: 3310 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 420
Production: Size feet:
Liner: Size feet:

107.58

Well Type: DH UIC Docket No: Date/Time to Plug: 11/26/2000 11:00 PM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: BESSIE Company: L.D. DRILLING, INC. Phone: (316) 793-3051

Proposed Plugging Method: Ordered 155 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/27/2000 1:45 AM

KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3281' w/25 sxs. Arbuckle 3281'
2nd. Plug at 725' w/25 sxs. Anhydrite 692' - 723'.
3rd. Plug at 475' w/80 sxs. Surface pipe to 420'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 02 2001

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed [Signature]

(TECHNICIAN)

INVOICED

DATE 1/3/01

INV. NO. 2001061222

Form CP-2/3

DEC 28 2000