

To: **6 062073**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5070

Operator: Davies and Company Inc.
Name & Address 2653 So. Birmingham
Tulsa, Ok. 74114

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gressel Corporation License Number 5822

Address 1103 So. St. John, Lyons, Ks. 67554

Company to plug at: Hour: 10:30AM Day: 5 Month: Feb Year: 19 90

Plugging proposal received from Mr. Gressel

(company name) Gressel Corp (phone) 316-257-5570

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 Day: 5 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 387' w/189 sks. 4 1/2" set at 2446' w/150 sks.

Top perf at 2256'. Plugged bottom w/sand and 4 sks cement to 2195'. Shot pipe one time

and recovered 1610'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks

cement w/600 psi.

RECEIVED
STATE CORPORATION COMMISSION

02-14-90
FEB 14 1990

Remarks: B: Allied. Ran line to 1000'.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
observe this plugging.

DATE 2-15-90

INV. NO. 27450

Signed Gilbert G. Scheck

(TECHNICIAN)

Gilbert G. Scheck