

4-071117

8-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-23,088-00-00

NE NE SE /4 SEC. 32, 14 S, 15 W
2310 feet from S section line
330 feet from E section line

Operator license# 6227

Lease Hertel well # 1

Operator: Prospect Oil & Gas Company

County Russell

Address: P.O. Box 837
Russell, Kansas 67665
Brad Hutchinson

Well total depth 3400 feet ^{110.50}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 233 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Drilling - Allied Cement License#

Address: Russell, Kansas 67665 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 30 Month: August Year: 94

Plugging proposal received from: Tom Alm

Company: Emphasis Drilling Phone: 913-483-6266

Were: 8 5/8" - 233' S.P. cwc. w/140 sxs. 60/40 pozmix - 2% gel - 3% c.c. No ar buckle - Elev. 1900' - Anhy. 959' - No circulations problems Mud condition 47 vis. - 9.3 wt. - 8.0 water loss - 4000 ppm cl. @ 3215'. Proposal circulate hole, order 180 sxs. 60/40 pozmix - 6% gel. Pump in with pump truck. Spot and displace all cement through drill pipe. Heavy mud between all plugs. No ar buckle. 25 sxs. cmt. @ 960' - 80 sxs. cmt. @ 550' - 40 sxs. @ 270' - 10 sxs. cmt. @ 40' - 15 sxs. in rathole (circulate) - 10 sxs. in mousehole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:00A.M., Day: 30, Month: August, Year: 94

Actual plugging report: Emphasis ordered 180 sxs. 60/40 pozmix - 6% gel and 1/4# F.C. per sack. Pumped in with pump truck - spotted and displaced all cement through drill pipe with heavy mud between all plugs.

1st. plug at 960' w/25 sxs. cement.

2nd. plug at 550' w/80 sxs. cement.

3rd. plug at 270' w/40 sxs. cement.

4th. plug at 40' w/10 sxs. cement.

15 sxs. in rathole (circulated) - 10 sxs. in mousehole (circulated)

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1900 GL

I did[] / did-not[X] observe the plugging.

Marion J. Schmidt
(agent)

DATE SEP 12 1994

WV. NO. 41195

RECEIVED
STATE CORPORATION COMMISSION

SEP 06 1994

CONSERVATION DIVISION
WICHITA, KANSAS