

6 070149

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

100' E API NUMBER 15- 167-22,363 - 00-00
NE NE NW, SEC. 21, T. 14 S, R. 15 (W) Ex
330 feet from N/8 section line
2210 feet from W/8 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6194

Operator: ESP Development, Inc.

Name: % Lewis Eulert

Address: Paradise, Ks. 67658

Lease Name J.W. Schmitt Well # 1

County Russell

Well Total Depth 3370 109.53 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8^{5/8} feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Drilling, Inc. License Number 8241

Address P.O. BOX 506 Russell, Ks. 67665

Company to plug at: Hour: 6 AM Day: 16 Month: May Year: 19 84

Plugging proposal received from Ray Goans

(company name) Emphasis Drilling Company, Inc. (phone) (913) 998-4413

were: 8^{5/8}" 259' SP CUC w/165 sks common 2% gel 3% cal. cl. by Allied Cementing CompanyOrder 200 sks 50/50 pozmix 4% gel 3% cal. cl. 1 sk cello flake, and 8^{5/8}" plug. Spot with

drillstem, turn hole over, heavy mud between all plugs. No circulation problems.

Arbuckle @ 3338' Elevation 1849' Anhy 912'

Plugging Proposal Received by Michael Schmitt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 PM Day: 16 Month: May Year: 19 84

ACTUAL PLUGGING REPORT Cemented by Allied Cementing Company

1st plug @ 3300' w/25 sks cmt

2nd plug @ 930' w/25 sks cmt

3rd plug @ 570' w/80 sks cmt w/1 sk cello-flake

4th plug @ 270' w/50 sks cmt

5th plug solid bridge hulls plug @ 40' to 0 w/10 sks cmt

Remarks: 10 sks in Rat Hole (Circulate)

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 5-22-84

INV. NO. 1609

Signed Michael Schmitt
DOIC (TECHNICIAN)RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1984

CONSERVATION DIVISION
Wichita, Kansas