

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-0-51-23, 520-00-00

NW, SEC. 6, T14S, R16W

990 FEET FROM N/SECTION LINE

330 FEET FROM W/SECTION LINE

LEASE NAME Hipes WELL # 1

COUNTY Ellis

WELL TOTAL DEPTH 3527 114.63 FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 203 W/125

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Helberg Oil LICENSE NUMBER 5659

ADDRESS Box 32, Morland, Ks.

COMPANY TO PLUG AT: HOUR: 4:00 AM DAY: 14 MONTH: 7 YEAR: 19 83

PLUGGING PROPOSAL RECIEVED FROM Buster Weibert

(COMPANY NAME) Weibert Enterprises (PHONE) 913-628-3324

WERE: Order 180 sh. 50 gr. mix - 4 7/8" - 3 7/8" - 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs.

PLUGGING PROPOSAL RECEIVED BY Arthur E. Schuch
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 4:00 AM DAY: 14 MONTH: 7 YEAR: 19 83

ACTUAL PLUGGING REPORT 1st plug C 3500' w/ 20 sh.

2nd plug C 1100' w/ 20 sh.

3rd plug C 600' w/ 80 sh.

4th plug C 250' w/ 40 sh.

5th plug Solid bridge of shells & plug C 40' w/ 10 sh.

Circulated 10 sh. in rat hole.

REMARKS: Elev. 1970' By Sun Oilwell Cementing Co. Inc.

Only 1111'

Drilled into Arbuckle.

I ~~(DID)~~ DID NOT OBSERVE THIS PLUGGING.

SIGNED Arthur E. Schuch
(TECHNICIAN) ✓

INVOICED

DATE 7-26-83

INV. NO. 4972-W

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1983
07-18-83
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 6-83