

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22205-00-00
Spot: CSENE Sec/Twnshp/Rge: 16-14S-12W
990 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: PASEK Well Number: 1
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 3134 Conductor Pipe: Size _____ feet: 8/08.55
Op Name: MORRIS, TERRY E. DBA G L M COMPAN Surface Casing: Size 8.625 feet: 406
Address: PO BOX 193 Production: Size 5.5 feet: 3339
RUSSELL, KS 67665 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/29/2002 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/29/2002 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2800' and dumped 5 sxs cement.
Shot off casing at 1653'.
Pulled to 1350' - pumped 90 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled to 650' - pumped 40 sxs cement with 100# hulls.
Pulled to 200' - circulated with 40 sxs cement.

RECEIVED
12-05-2002
DEC 05 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

01

Signed _____

Case Morris

(TECHNICIAN)


INVOICED Form CP-2/3

DATE 12-5-02

INV. NO. 2003060919

DEC 04 2002

CUSTOM OIL EXPLORATION #1 PASEK 16-14-12W
 P.O. BOX 305 SE NE NE
 CHASE, KS 67524
 CONTR. DUKE DRILLING CO. CTY RUSSELL
 GEOL. FIELD BEISEL EXT (1/8 W)
 ELV 1775 KB SPD 9/2/83 CARD ISSUED 2/21/85 IP OIL WELL
 WAB(TARK) - INTV NA



API 15-167-22,205

LOG	Tops	Depth/Datum
GR HAVEN	2225- 450
TARK	2300- 525
TOP	2572- 797
HEEB	2811-1036
TOR	2832-1057
DOUG	2847-1072
LANS	2896-1121
BKC	3174-1399
PENN-CONG	3233-1458
GOR	3260-1485
ARB	3274-1499
RTD	3340-1565

8 5/8 " 406, 5 1/2 " 3339
 DST (1) 2185-2346 (WAB) / 30-30-30-30, REC 320' SGCM, SIP
 638-628#, FP 98-127 / 156-166#, HP 1176-1136#, BHT 90°
 MICT -CO, PF (GOR) INTV NA, SWB DWN, SO, NON-COMMER-
 CIAL, SET BP ABOVE GOR PFS (DEPTH NA), PF (LKC) INTV NA,
 SWB DWN & REC 80 BF (20% OIL), POP, P 25 BOPD & LOTS OF
 WTR, TOO MUCH WTR, SD, OFF PMP, MICT CO, PF (ARB) INTV
 NA, SWB DWN, GSO, TOO MUCH WTR, PB (DEPTH NA), PF
 (TARK) INTV NA, SWB DWN, SO, FRAC'D (AMTS NA), SWB DWN,
 SO, POP -NO OTHER INFO TO BE RELEASED AT PRESENT -WILL
 RELEASE INFO WHEN AVAILABLE -TEMP COMP 2/21/85