

3-13

153

R

To: **6 062371**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,965-0000  
SE, SEC. 16, T. 14 S, R. 12 W/EX

**TECHNICIAN'S PLUGGING REPORT**

Operator License # 6246  
Operator: Bennett and Schulte Oil Co  
Name & Address 112 West 7th Street  
Russell, Ks. 67665

2310 feet from S section line  
330 feet from E section line  
Lease Name Teppe A Well # 4  
County Russell 104.74  
Well Total Depth 3223 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A xx

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241  
Address Russell, Ks. 67665

Company to plug at: Hour: 4:10 PM Day: 11 Month: Mar Year: 19 91

Plugging proposal received from Allen Langhoffer

(company name) Emphasis Oil Oper (phone) 913-0483-2721

were: Order 165 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8 plug.

Spot with drill pipe w/no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:00PM Day: 13 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 650 w/60 sks  
2nd plug at 500 w/40 sks  
3rd plug at 300 w/40 sks  
4th plug at 40 w/10 sks  
15 sks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
03-22-1991  
MAR 22 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cement  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If desired, check) observe this plugging.  
APR 02 1991

Signed Gilbert G. Scheck  
(TECHNICIAN)

Gilbert G. Scheck

DATE \_\_\_\_\_  
DIV. NO. 31258