

9-3

177  
P

6-070943

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-22.241-00-00

SE SE SE /4 SEC. 16, 14 S, 12 W  
330 feet from S section line  
330 feet from E section line

Operator license# 6246 Lease Teppe well # B#2

Operator: Bennett & Schulte Oil Co. County Russell 106.11

Address: P.O. Box 329 Well total depth 3265 feet  
140 W. Wichita Av. Conductor Pipe: 0 inch @ 0 feet  
Russell, Kansas 67665 Surface pipe 8 5/8 Inch @ 611 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing Company License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 3 Month: September Year: 91

Plugging proposal received from: Reginal Bennett

Company: Bennett & Schulte phone: 913-483-2721

Were: 8 5/8" 611' S.P. cvc. w/300 sx. cement. 5 1/2" casing set  
@ 3264' w/100 sx. cement. Perfs @ 2931 - 3039' - at bottom sand to  
to 2858' w/5 sx. cement. Recovered 1438' - 5 1/2" casing. Proposal  
225 sx. 65/35 poz. - 8% gel. - 5 sx. hulls. Pump in 8 5/8" with pump  
truck. 15 sx. cement then remainder of cement w/5 sx. hulls. Shut  
in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All  ], Part  ], None  ]

Completed: Hour: 11:15A.M., Day: 3, Month: September, Year: 91

Actual plugging report: Bennett & Schulte Oil ordered 225 sx. 65/35  
poz. - 8% gel. - 5 sx. hulls. Allied Cement pumped in 8 5/8" surface  
pipe w/15 sx. cement followed w/210 sx. cement w/1 sx. hulls. Max.  
pressure 600 P.S.I., shut in @ 400 P.S.I. Cemented by Allied Cement, RECEIVED  
Russell, Kansas. STATE CORPORATION COMMISSION

Remarks:    

OCT 01 1991  
10:01 1991  
CONSERVATION DIVISION  
Wichita, Kansas

I  ] did not  ] observe the plugging.

**INVOICED**

*Marion J. Schmidt*

DATE 10-8-91

(agent)

INV. NO. 333012

Form CP-2/3

9-3