

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-21,338-00-00

LEASE NAME Paul B. Biesel

WELL NUMBER 1-7

4270 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 7 TWP. 14S RGE. 11W (E) or (W)

COUNTY Russell

Date Well Completed 12/16/79

Plugging Commenced 2/3/90

Plugging Completed 2/5/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DAVIES & COMPANY, INC.

ADDRESS 2653 So. Birmingham Pl. - Tulsa, Okl. 74114

PHONE# (018)743-3029 OPERATORS LICENSE NO. 5070

Character of Well Depleted Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/30/90 (date)

by Gilbert Schuck (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? Filed w/ plugging application

Producing Formation Tarkio Depth to Top 2183 Bottom 2287 T.D. 2360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Tarkio	Gas	2183	2287	4-1/2	2360	1585

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded back to 2150' - Dump w/ bailer 5 sacks Cement - to 2100' - Mud Laden fluid 2100' - 1000' - 25 sacks 60/40 Pozmix - 8% gel + 5 sacks Hulls - Followed w/ 175 sacks 60/40 Poz Cement 8% Gel - Pumped by Allied Cement Co. - Pressure 1200# - Shut in 400# - Inv # 8588

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corporation License No. 5822

Address 1103 So. St. John - Lyons, Ks. - 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davies & Company Inc.

STATE OF Kansas COUNTY OF Butler, ss.

Ed Leith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

1509 Robin Ridge Cr.

(Address) Wichita, Ks. 67230

before me this 13th day of Feb, 1990

Deborah K Bollig
Notary Public

My Commission Expires: Nov 17, 1991

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1990
02-15-90
CONSERVATION DIVISION
Wichita, Kansas

DEBORAH K BOLLIG
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. _____

15-167-21338-00-00

Petro-Log

Compensated Density

COMPANY DAVIES & COMPANY, INC.

WELL BIESEL #1-7

FIELD _____

COUNTY RUSSELL **STATE** KANSAS

Location
Sec. 7 **Twp.** 14S **Rge.** 11W

Other Services:
RAG

Permanent Datum: GROUND LEVEL **Elev.** N.A.
Log Measured From KB **Ft. Above Perm. Datum** _____
Drilling Measured From KELLY BUSHING

Elev.: **K.B.** 1747 **N.A.** _____
D.P. N.A. _____
G.L. N.A. _____
1742

Date	7/30/79				
Run No.	ONE				
Depth—Driller	2360				
Depth—Logger	2356				
Btm. Log Inter.	2355				
Top Log Inter.	1300				
Casing—Driller	8 5/8 @ 301	•	•	•	•
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	STARCH				
Dens. Visc.	10.3 41				
pH Fluid Loss	6.0 13.6ml		ml		ml
Source of Sample	FLOWLINE				
R₁₀ @ Meas. Temp.	.08 @ 88 °F	@ °F	@ °F	@ °F	@ °F
R₁₀₀ @ Meas. Temp.	.06 @ 88 °F	@ °F	@ °F	@ °F	@ °F
R₁₀₀₀ @ Meas. Temp.	.12 @ 88 °F	@ °F	@ °F	@ °F	@ °F
Source: R₁₀ R₁₀₀ R₁₀₀₀	M M				
R₁₀ @ BHT	.07 @ 101 °F	@ °F	@ °F	@ °F	@ °F
Time Since Circ.	3 HOURS				
Max. Rec. Temp.	101 °F	°F	°F	°F	°F
Equip. Location	H-8 GB				
Recorded By	DENNIS COMER				
Witnessed By	MR. DICK GREEN				