

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
312 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Russell County, Sec. 6 Twp. 14 Rge. 11 (E) (W) X

Location as "NE/CNW/SE" or footage from lines SW NW SE
Lease Owner American Drilling Company, Ltd.
Lease Name Beisel Well No. 1
Office Address 360 Sutton Place Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 12-11-70 19
Application for plugging approved 12-12-70 19
Plugging commenced 12-29-70 19
Plugging completed 1-7-71 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3354 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	314	None
				4 1/2	3020	1537'.63

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Killed gas. Pushed a plug down to 2100'; dumped 30 gallons of sand and 4 sacks of cement. Had 15" tension at 1600 psi. Shot casing at 1631' and 1531'. Laid down 46 joints of casing. Sun Cementing squeezed well with 3 sacks of hulls, 20 sacks of gel and 90 sacks of 50/50 pozmix cement with 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 12 day of January, 1971



(Signature) Notary Public.

My commission expires May 27, 1973

15-167-20243-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

COMPANY: American Drilling Company
 CONTRACTOR: American Drilling Company
 FARM: No. 1 Beisel
 LOCATION: SW NW SE, Section 6-14S-11W
 Russell County, Kansas
 COMMENCED: December 27, 1968
 COMPLETED: January 8, 1969

FORMATION	DEPTH	
Surface Soil	0 to 30'	Elevation: 1810' K.B. - 1807' D.F.
Red Bed	30 to 314'	
Shale	314 to 656'	Spudded surface hole @ 9:00 P.M. 12-28-68.
Anhydrite	656 to 690'	Drilled 12-1/4" surface hole to 314'.
Shale	690 to 1340'	Set 8-5/8" casing at 314', cemented with
Lime & Shale	1340 to 1705'	175 sxs. cement. Plug down at 4:00 P.M.
Lime	1705 to 1830'	12-29-68.
Lime & Shale	1830 to 2800'	
Lime	2800 to 3024'	DST #1: 2215-2287'
Lime & Shale	3024 to 3060'	DST #2: 2941-2951'
Lime	3060 to 3230'	DST #3: 3010-3024'
Lime & Shale	3230 to 3301'	
Lime	3301 to 3354'	Set 4-1/2" production casing at 3020',
RTD	3354'	cemented with 400 sxs. 60-40 Pozmix, 1%Gel.

Job completed at 9:30 P.M. 1-8-69.


FORMATION TOPS (Sample)

Topeka	2550	- 750'
Heebner	2826	-1016'
Brown Lime	2910	-1102'
Lansing	2925	-1115'
Base Kansas City	3213	-1403'
Conglomerate	3261	-1451'
Arbuckle	3300	-1490'
RTD	3354	-1544'

A F F I D A V I T

STATE OF KANSAS
COUNTY OF SEDGWICK

I, Larry G. Stephenson, of the American Drilling Company, do hereby certify and state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


Larry G. Stephenson

DEC 8 1970