

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-21,463-00-00

LEASE NAME Paul B. Biesel

WELL NUMBER 1-6

1320 Ft. from S Section Line

4455 Ft. from E Section Line

SEC. 6 TWP. 14 RGE. 11W (E) or (W)

COUNTY Russell

Date Well Completed 12/16/80

Plugging Commenced 2/1/90

Plugging Completed 2/5/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DAVIES & COMPANY, INC.

ADDRESS 2653 So. Birmingham Pl. - Tulsa, Ok. 74114

PHONE# (918) 743-3029 OPERATORS LICENSE NO. 5070

Character of Well Depleted Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/30/90 (date)

by Gilbert Schuck (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? Filed w/ application

Producing Formation Tarkio Depth to Top 2256 Bottom 2359 T.D. 2447

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Tarkio	Gas	2256	2359	4-1/2	2246	1610

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sand back to 2195' - Dump 5 sacks cement w/ dump bailer - to 2140' - Mud laden fluid  
2140' to 1000' - Pump 25 sacks 60/40 Poz. cement 8% Gel - 5 sacks Hulls - 175 sacks  
60/40 Poz, 8% Gel - Pumped @ 600# - Shut in 300# - Plugging complete 2/5/90 - 2:00 PM  
Cementing by Allied Cement Co. - Inv. # 8587  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corporation License No. 5822

Address 1103 So. St. John - Lyons, Ks. - 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davies & Company, Inc.

STATE OF Kansas COUNTY OF Butler, ss.

Ed Leith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
02-15-90

(Signature) Ed Leith

(Address) 1509 Robin Ridge Dr Wichita, KS

SUBSCRIBED AND SWORN TO  
CONSERVATION DIVISION  
Wichita, Kansas  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. Nov 17, 1991

before me this 13th day of Feb, 1990

Deborah K. Bolding  
Notary Public

15-167-21463-00-00

# Netro-Log

# Radiation Guard Log

COMPANY DAVIES AND COMPANY, INC.

WELL BEISEL #1-6

FIELD \_\_\_\_\_

COUNTY RUSSELL STATE KANSAS

Location C/W/2-E/2

Other Services: CDL

Sec. 6 Twp. 14S Rge. 11W

Permanent Datum: GROUND LEVEL Elev. 1814.2

Log Measured From K, B, 7.8 Ft. Above Perm. Datum

Drilling Measured From KELLY BUSHING

Elev.: K.B. 1822  
D.F. \_\_\_\_\_  
G.L. 1814.

Date	7/31/80					
Run No.	ONE					
Depth—Driller	3006					
Depth—Logger	3004					
Btm. Log Inter.	3003					
Top Log Inter.	SURF.					
Casing—Driller	8 5/8	@	387	@	@	@
Casing—Logger						
Bit Size	7 7/8					
Type Fluid in Hole	STARCH					
Dens.	Visc.	10.1	49			
pH	Fluid Loss	6.4	111.0ml	ml	ml	ml
Source of Sample	FLOWLINE					
R <sub>1</sub> @ Meas. Temp.	.1	@	90°F	STATE @ 100°F	@	*F @
R <sub>2</sub> @ Meas. Temp.	.07	@	90°F	@ 100°F	@	*F @
R <sub>3</sub> @ Meas. Temp.	.15	@	90°F	@ 100°F	@	*F @
Source: R <sub>1</sub> R <sub>2</sub> R <sub>3</sub>	CHARTIS			4-4 1009		
R <sub>4</sub> @ BHT	.08	@	107°F	@ 100°F	@	*F @
Time Since Circ.	2 HRS.					
Max. Rec. Temp.	107°F					
Equip.   Location	H-10		GB			
Recorded By	J. MAYERS AND L. LEWIS					
Witnessed By	MR. DICK GREEN					