

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-21,328-00-00

LEASE NAME Ernest Veverka

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-2

660 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR DAVIES & COMPANY, INC.

SEC. 2 TWP. 14S RGE. 11W (E) or (W)

ADDRESS 2653 So. Birmingham Pl. - Tulsa, Ok 74114

COUNTY Russell

PHONE# (918) 743-3029 OPERATORS LICENSE NO. 5070

Date Well Completed 11/15/79

Character of Well Depleted Gas

Plugging Commenced 1/30/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/5/90

The plugging proposal was approved on 1/30/90 (date)

by Gilbert Schuck (KCC District Agent's Name).

Is ACO-1 filled? NA If not, is well log attached? Filed w/ application

Producing Formation Tarkio Depth to Top 2232 Bottom 2277 T.D. 2310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Tarkio	Gas	2232	2277	4-1/2	2385	1730

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
SAnd back to 2175' - Dump 5 sacks cement w/ bailer -2175' to 2110' - Mud laden fluid  
2110' to 1000' - Pumped 25 sacks 60/40 Poz 8% Gel - 5 Sacks Hulls - 175 Sacks 60/40 Poz.  
8% Gel - Pumped in @ 900# - Shut in @ 400# - Plugging Complete 11:45 AM 2-5-90  
Cementing service performed by Allied Cementing Co. Inv # 8586.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corporation License No. 5822

Address 1103 So. St. John - Lyons, Ks. 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davies & Company Inc.

STATE OF Kansas COUNTY OF Butler, ss.

Ed Leith

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

1509 Robin Ridge Cr.

(Address) Wichita, Ks. 67230

before me this 13th day of Feb, 1990

RECEIVED  
STATE CORPORATION COMMISSION  
02-15-90

FEB 15 1990  
DEBORAH K. BOLLIG  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. \_\_\_\_\_

Deborah K. Bollig  
Notary Public

Commission Expires: Nov 17, 1991

15-167-21328-00-00

# Petro-Log

## Compensated Density

COMPANY DAVIES AND COMPANY, INC.

WELL ~~VEE-100-1167~~

FIELD \_\_\_\_\_

COUNTY RUSSELL STATE KANSAS

Location <u>C-SE-SW</u>	Other Services: <u>RAG</u>
Sec. <u>2</u> Twp. <u>14S</u> Rge. <u>11W</u>	

Permanent Datum: <u>GROUND LEVEL</u> Elev. <u>NA</u>	Elev.: K.B. <u>1808</u>
Log Measured From <u>KB</u> , <u>NA</u> Ft. Above Perm. Datum	<u>1805</u> D.F.
Drilling Measured From <u>KEYLY BUSHING</u>	<u>1803</u> G.L.

Date	8/14/79					
Run No.	ONE					
Depth—Driller	2415					
Depth—Logger	2415					
Btm. Log Inter.	2412					
Top Log Inter.	1700					
Casing—Driller	8 5/8	@ 302	@	@	@	@
Casing—Logger						
Bit Size	7 7/8					
Type Fluid in Hole	STARCH					
Dens.	10.2	46				
pH	5	14.6 ml	10 ml		ml	ml
Source of Sample	FLOWLINE					
R <sub>100</sub> @ Meas. Temp.	.08	@ 82°F	@	@	@	@
R <sub>100</sub> @ Meas. Temp.	.06	@ 82°F	@	@	@	@
R <sub>100</sub> @ Meas. Temp.	.12	@ 82°F	@	@	@	@
Source: R <sub>100</sub> R <sub>100</sub>	CHARTS					
R <sub>100</sub> @ BHT	.07	@ 102°F	@	@	@	@
Time Since Circ.	5 HRS.					
Max. Rec. Temp.	102°F		@	@	@	@
Equip.   Location	H-5	GB				
Recorded By	BYRON WINCHESTER					
Witnessed By	MR. GREEN					