

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-22792-00-00

LEASE NAME LEIKER-SCHRANT

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 30 TWP. 14S RGE. 15 (E) or (W)

COUNTY RUSSELL

Date Well Completed 11-6-87

Plugging Commenced 11-24-98

Plugging Completed 11-24-98

LEASE OPERATOR T.D.I. OIL OPERATIONS

ADDRESS 1310 BISON ROAD HAYS, KS 67601

PHONE# (785) 628-2593 OPERATORS LICENSE NO. 4787

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-22-98 (date)

by HERB DEINES (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation TORONTO, CONG Depth to Top 3012' Bottom 3279' T.D. 3355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	232	8/5/8	232	0
		surface	3352	5 1/2	3352	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
RUN TBG TO 2900' PUMP 12 SX GEL FOLLOWED W/ 25sx gel W/ 100# HULLS. PUMP 50 SX CEMENT W/ 100# HULLS. PULLED TBG TO 1525'. CIRC 50 SX CEMENT W/ 80 SX CEMENT W/ 300# HULLS. PULL TBG. PUMPED DOWN CSG W/ 45 SX CEMENT. MAX PRESSURE 500#. SHUT IN PRESSURE 400#. PUMPED UP TO 300# ON ANNULUS - WOULD NOT TAKE CEMENT.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor T.D.I. OIL OPERATIONS License No. 4787 12-15-98

Address 1310 BISON ROAD HAYS, KS 67601-96969

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: T.D.I. OIL OPERATIONS

STATE OF KANSAS COUNTY OF ELLIS, ss.

DEB DENNING

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Deb Denning

(Address) 1310 BISON RD HAYS, KS 67601

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 98

Carol Romme

My Commission Expires: 5-3-2002

Notary Public
NOTARY PUBLIC - State of Kansas
CAROL ROMME
My Appt. Exp. 5-3-2002