


15-109-00012-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Logan County, Sec. 6 Twp. 14S Rge. 37 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW NW
Lease Owner The Shamrock Oil and Gas Corporation
Lease Name R. F. Surratt "D" Well No. 1
Office Address Box 631, Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-26 19 58
Application for plugging filed 10-26 19 58
Application for plugging approved 10-26 19 58
Plugging commenced 12 Noon 10-26 19 58
Plugging completed 7 P.M. 10-26 19 58
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker (C)
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4989' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
No water sands				8 5/8"	240	=0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed 8 5/8" OD Halliburton plug to 600'. Spotted 20 sacks of cement at 600'. Filled hole with heavy rotary mud. Pushed 8 5/8" OD plug to 240'. Dumped 1/2 sack of hulls on plug. Spotted 20 sacks cement at 240'. Filled hole with heavy mud. Pushed plug to 40'. Dumped 1/2 sack hulls on plug. Filled hole with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1958

DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Great Bend, Kansas

STATE OF TEXAS, COUNTY OF POTTER, ss.
T. S. Clopton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. S. Clopton
Box 631, Amarillo, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 58

PAULINE POWELL
Notary Public
Potter County, Texas Notary Public.

My commission expires 6-1-59

PLUGGING
FILE SEC. 6 T. 14 R. 37 W
BOOK PAGE 140 LINE 32

Shenandoah Oil & Gas

SURRATT "D" NO. 1
Logan County, Kansas

6-14-37 W
NW NW NW

Dry

0' - 60'	Surface soil and clay
60' - 90'	Sand and shale
90' - 400'	Shale
400' - 1,560'	Shale and shells
1,560' - 1,650'	Shale
1,650' - 1,700'	Sand and shale
1,700' - 1,760'	Shale
1,760' - 1,785'	Anhydrite
1,785' - 2,020'	Shale
2,020' - 2,500'	Red bed & shale
2,500' - 2,620'	Salt & shale
2,620' - 3,095'	Lime and shale
3,095' - 3,335'	Lime
3,335' - 3,440'	Lime and chert
3,440' - 3,559'	Lime and shale
3,559' - 3,630'	Lime
3,630' - 3,660'	Shale
3,660' - 3,990'	Lime
3,990' - 4,060'	Lime and chat
4,060' - 4,230'	Lime
4,230' - 4,420'	Lime & chat
4,420' - 4,510'	Lime
4,510' - 4,650'	Lime & chat
4,650' - 4,670'	Shale
4,670' - 4,690'	Lime
4,690' - 4,700'	Shale
4,700' - 4,805'	Lime w/ shale streaks
4,805' - 4,810'	Sand
4,810' - 4,875'	Lime w/ shale streaks
4,875' - 4,920'	Shale
4,920' - 4,925'	Sand
4,925' - 4,989'	Lime w/ sand streaks

[Faint, illegible text]

PLUGGING	
FILE SEC.	6 7 14 R37W
BOOK PAGE	140 LINE 32

15-109-00012-00-00

THE SHAMROCK OIL AND GAS CORPORATION

AMARILLO, TEXAS

Ship To:
In Care Of:
Via:
F. O. B.

ORDER No. 240511

Req. No. 4-13301
Date 11-5-58

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
212 N. MARKET
WICHITA 2, KANSAS

Mail INVOICE in QUADRUPLICATE and BILL OF LADING to THE SHAMROCK OIL AND GAS CORPORATION, AMARILLO, TEXAS. Accompany each delivery of goods with an itemized delivery memo (not an invoice) bearing our order number. MAIL MONTHLY STATEMENT to OFFICE OF THE COMPANY, AT AMARILLO, TEXAS.

QUANTITY	MATERIAL	PRICE
	For Plugging Surratt "D" No. 1 CNW NW NW 6-14-37W - Logan Co., Kansas File No. 140-32	\$ 48.98
<p>RECEIVED STATE CORPORATION COMMISSION NOV 6 1958 CONSERVATION DIVISION Wichita, Kansas</p> <p>CONFIRMATION ONLY DO NOT DUPLICATE</p>		
CONFIRMING INVOICE		
PURCHASE ORDER		

ORIGINAL

IMPORTANT! ALL INVOICES MUST SHOW ORDER NUMBER

Acknowledge receipt of this order at once, advising shipping date and any incorrectness in prices. Address all communications with references to this order to Purchasing Agent, Amarillo, Texas. NO ALLOWANCE FOR BOXING OR CARTAGE UNLESS SPECIFIED.

CHARGE TO: EW #424 - Surratt "D" #1

THE SHAMROCK OIL AND GAS CORPORATION

By J. C. Wilkerson
J. C. WILKERSON