

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-109-20496-00-00

LEASE NAME Dirks

WELL NUMBER 23-1

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 23 TWP. 14S RGE 335 (E) or (W)

COUNTY Logan

Date Well Completed NA

Plugging Commenced 1/28/91

Plugging Completed 1/30/91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Holden Energy Corporation

ADDRESS Suite 600 - Lincoln Center, Ardmore, OK 73401

PHONE# (405) 226-3960 OPERATORS LICENSE NO. 30575

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/28/91 (date)

by Carl Goodroe (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, Is well log attached? _____

Producing Formation Dry Depth to Top ---- Bottom ---- T.D. 4907

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss	Dry	4802	414			
Cherokee	Dry	4576	82	8 5/8	269	None
Marmaton	Dry			4 1/2	4901	3163'
Lansing	Dry	3957	4536			

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP-4763, CIBP-4550, Cement Plug (3500-4536) 70 sks. cement blend w/200# Hulls (Maintain Pos. Press.) Ran FreePoint. Shut off 4 1/2 Csg. 3163. Laid dn. 4 1/2 to 2550. Pump 115 sk. Cement Plug. Laid dn 4 1/2 csg. Sq. 8 5/8 Casing w/total of 300 sks. cement blend w/500# Hulls (SI Press. 150 PSIG) P & A Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Servicing Inc. License No. 3152

Address P. O. Box 218, Oakley, Kansas 67748

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Holden Energy Corporation

STATE OF Oklahoma COUNTY OF Carter, ss.

C. G. Mason


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

C. G. Mason, Production Supt.
Suite 600 - Lincoln Center, Ardmore, OK 73401

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1991



John J. [Signature]
 Notary Public

My Commission Expires: October 13, 1993

RECEIVED
 STATE CORPORATION COMMISSION
 02-08-91
 FFR 8 1991