

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,289-00-00

LEASE NAME Peters "F" #2

WELL NUMBER SE NE NW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 14s RGE. 33w(E) of (W)

COUNTY Logan

Date Well Completed

Plugging Commenced 5/1/85

Plugging Completed 5/6/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Donald C. Slawson

ADDRESS 200 Douglas Building, Wichita, Ks. 67202

PHONE# (316) 263-3201 OPERATORS LICENSE NO. 5181

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	345'	none
				4 1/2"	3945'	1020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3775' & 4 sacks cement. Shot pipe at 2503', 2028', 1509', 1342', & 1020'. Pulled 25 joints of pipe. Plugged well with 4 hulls with 30 gel, 100 sacks cement, 10 gel, released plug, & 80 sacks 50/50 poz 6% gel 3% c.c. Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No.

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 85

Jane Hoover
Notary Public

My Commission Expires:



15-109-20289-00-00

DONALD C. SLAWSON

WELL RECORD

LEASE Peters F Well No. 2
 OPERATOR Donald C. Slawson
 LOCATION SE-NE-NW
 SECTION 36 TWP 14s RANGE 33w
 SURVEY _____ BLOCK _____ SECTION _____
 COUNTY Logan STATE Kansas
 STAKED BY L & S DATE 3-23-83 ELEVATION 2835 KB

TOOLS	STARTED	COMPLETED	FROM	TO	CONTRACTOR
ROTARY	7-13-83	7-26-83	0	4550'	Slawson Drlg. Co. Rig # 3
COMPLETION	8-4-83	8-12-83			Poe Well Serv.

OPEN HOLE LOGS <u>Yes, Dresser Atlas</u>	FORMATION
COMPLETION INTERVALS <u>Perf 38³⁹-3845 w/2 Jumbo jets per ft</u>	KC
	PBTD 3898

CASING, TUBING AND RODS

JOINTS	SIZE	WT	COUPLING	GRADE NEW/USED	SETTING DEPTH	CEMENT		REMARKS
						SACKS	EST. TOP	
8	8 5/8	24#		New	345	225	G.L.	Did Circ.
97	4 1/2	10.5		New	3945	125	G.L.	Did not circ.
121	2-3/8	4.7		Used	3806 w/15'			mud anchor top 2' perf
151	3/4" used rds		1-2' 3/4"	pony rd				
	2" x 1 1/2 x 12'	metal	pp					
	16' 1 1/2	polish	rd					

STIMULATION RECORD

Treatment Frac / Acid	Acid	Acid		
Date	8-5-83	8-10-83		
Quantity (Gals.)	1250	500		
Type	NE 28%	NE 28%		
Proppant				
Tubing / Casing	CSG	CSG		
Breakdown Pressure	150	200		
Treat Pressure	150-175	200-400		
Instant SIP	100	150		
Total Bbls. Load	106	106		
Flush Agent	SW	SW		
Oil/Gas Before	1.24 BPH	0		
Oil/Gas After	100% W	35 BPH		
Water Before	24%	0		
Water After	100% W	54%		
Done By	Halliburton Halliburton			

PUMPING UNIT

Manufacturer Lufkin
 Size 114
 Serial No. F744 96J 426638
 PRIME MOVER APR 15 1983
 Manufacturer CE
 Size 66
 Serial No. 84 475

TANK BATTERY

1 - 10 x 16 FG GB Aug 15 1983
 2 - 12.6 stock tanks 03 1983
 1 - 12 x 10 FG W.T.
 3200' 2 1/2 PVC lead line