

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-109-00023-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR

Strike out upper line  
when reporting plugging  
of formations.

FORMATION PLUGGING RECORD

Logan County, Sec. 14 Twp. 14S Rge. (E) 33 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SE/4 SE/4 SW/4

Lease Owner Ashland Oil & Refining Company

Lease Name John W. Briggs Well No. 1

Office Address Box 1127, Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 15 19 52

Application for plugging filed October 15 19 52

Application for plugging approved October 15 19 52


Plugging commenced October 15 19 52

Plugging completed October 15 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation None Depth to top - Bottom - Total Depth of Well 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Fresh water	30'	35'	8-5/8"	155'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud to 150' from surface. Ran 15 sax cement at 150'. Filled hole to within 40' of surface and ran 10 sax cement. Job complete 10:00 p.m., 10-15-52.

(Drill pipe was used to introduce heavy mud into the hole and also to spot the cement plugs.)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 1 1952 11-01-52  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ashland Oil & Refining Company, Attn: A. G. Burki,  
Address Box 1127, Oklahoma City, Oklahoma

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
A. G. Burki (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. G. Burki*  
A. G. Burki  
Box 1127, Oklahoma City, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of October, 19 52

My commission expires 8/8/55

*Esther M. ...*  
Notary Public.

PLUGGING  
FILE SEC 14 T 14 S 33  
BOOK PAGE 54 LINE 3

WELL LOG

Ashland Oil & Refining Company

John W. Briggs #1  
C SE SE SW Sec.14, T-14S, R-1E  
Logan County, Kansas

0 - 35	Sand - River Gravel
35 - 151	Shale and Shells (Hard)
151 - 905	Shale, Sand and Chalk Shells
905 - 1340	Sand and Shale
1340 - 1485	Shale and Shells
1485 - 1510	Possible Anhydrite Lime
1510 - 1740	Red-Bed
1740 - 1750	Shale - Red Bed
1750 - 1800	Anhydrite
1800 - 1960	Red Bed - Shale, Gypsum
1960 - 2140	Red Bed Shale
2140 - 2180	Lime
2180 - 2200	Lime
2200 - 2390	Shale and Lime
2390 - 2670	Red-Bed and Shale
2670 - 2760	Lime and Shale
2760 - 2840	Lime
2840 - 2940	Lime and Shale
2940 - 3050	Shale and Lime
3050 - 3270	Shale
3270 - 3440	Shale and Lime
3440 - 3445	Lime
3445 - 3520	Lime and Shale
3520 - 3570	Lime
3570 - 4055	Lime and Shale
4055 - 4165	Lime
4165 - 4205	Hard Lime
4205 - 4235	Lime
4235 - 4260	Lime and Shale
4260 - 4300	Hard Lime
4300 - 4319	Lime
4319 - 4348	Sandy Shale
4348 - 4360	Lime
4360 - 4470	Hard Lime
4470 - 4500	Hard Lime

RECEIVED  
STATE COOPERATION COMMISSION  
NOV - 1 1952  
CONSERVATION DIVISION  
Wichita, Kansas

A F F I D A V I T

STATE OF Oklahoma, COUNTY OF Oklahoma, SS

I, A. G. Burki of the Ashland Oil & Refg. Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Subscribed and sworn to before me this 15 day of October 1952

*A. G. Burki*  
*Edwin M. ...*  
Notary Public

My Commission Expires: 8/8/55

PLUGGING  
FEE SEC 14 T 14 R 332  
BOOK PAGE 54 LINE 3