

4-050323

12-1

TO:

API Number: 15-051-23,805-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NW SW _____/4 SEC. 22, 14 S, 17 W
1650 _____ feet from S section line
4950 _____ feet from E section line

Operator license# 8729

Lease: Brull Well # 2

Operator: Hertel Oil Company

County: Ellis

114.24

Address: 704 East 12th Street
Hays, Kansas 67601
785-628-2445

Well total depth 3515 PBTB 3305 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing Company

License# _____

Address: _____

Company to plug at: Hour: A.M. Day: 1 Month: December Year: 1998

Plugging proposal received from: Dave Hertel

Company: _____

Phone: _____

Were: Order 225 sxs 60/40 pozmix 10% gel 500# hulls.

8 5/8" at 211' w/135 sxs. 4 1/2" at 3512' w/125 sxs.

Dakota squeeze with 350 sxs and Cedar Hills squeeze with 225 sxs.

Dakota 247' - 547'. Anhydrite 1110' - 1150'. Salt 1525' - 1810'.

Arbuckle open hole and LKC perfs 3270' - 3326'.

CIBP's at 3425' - 3305'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 12:00 P.M. Day: 1, Month: December, Year: 1998

Actual plugging report: Tied onto 4 1/2" casing. Pumped and squeezed with 175 sxs cement and 500# hulls. Max. P.S.I. 1000#. S.I.P. 600#. Backside full pressured to Max. P.S.I. 500#.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD X Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 1972 GL

I did [X] / did not [] observe the plugging.

Maurin Miller
(agent)

10

Form CP-2/3

RECEIVED
KANSAS CORP COM.
12-07-1998
1998 DEC -7 P 2:05


DEC 17 1998

60468

R. P. NIXON OPERATIONS
 207 W. 12TH STREET #2 BRULL
 HAYS, KS 67601
 22-14-17W
 SW NW SW

CONTR JAY-LAN CORPORATION CTY ELLIS
 GEOL DAN NIXON FIELD HEYL SF

ELV 1979 KB SPD 2/21/84 CARD ISSUED 8/23/84 IP P 12 BO & 80 BWPD
 1974 GL ARB OH 3512-3515



| SMP | Tops | Depth/Datum |
|--------|-------|-------------|
| ANH | | 1150+ 829 |
| B/ANH | | 1189+ 790 |
| HEEB | | 3200-1221 |
| TOR | | 3223-1244 |
| LANS | | 3244-1265 |
| BKC | | 3478-1499 |
| ARB | | 3510-1531 |
| RTD | | 3515-1536 |
| DDTD | | 3518-1539 |
| NO LOG | | |

API 15-051-23,805-00-00
 8 5/8 " 211, 4 1/2 " 3512
 NO DSTS
 MICT - CO. (ARB OH), AC 500G (MA), ONFU 500' OIL & 1700'
 AW, SWB DWN & REC 4 BFPH (50% OIL) / APPX 4 HRS. POP. P
 12 BO & 80 BWPD. 2/27/84

Perf 249-549
 Arb 1150-1189
 Set 1527-1812

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

4-85 Holes of 540 - 5.2 150ms
 200 ms to 1000'

5-86 Holes 866-900 592 260 L.S. Connect to 1000'

Casing Cap 150
 Perf 25
 ANN 50

275 60/caps 10' perf
 500# hulls.

CIBP#T 3425
 Arb at 3510

CIBP AT 3305

Perf 3270-74, 3290-93

11-04-1978

RECEIVED
 IANSS CORP COMM
 NOV-11 A 11:29

Appure by Herb Denis