

15-051-01493-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SEC. 22 T 14S, R 17 W

330 FEET FROM N SECTION LINE

330 FEET FROM W SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5245

LEASE NAME Younker WELL # 1

OPERATOR: Ohmer Oil Co
NAME & ADDRESS E. 8th st. Hays, Mo.
67601

COUNTY Ellis

WELL TOTAL DEPTH 3343 \$108.65 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 204'

ABANDONED OIL WELL ~~XXXX~~ GAS WELL _____ INPUT WELL _____ SWD WELL ~~XXXX~~ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Lucas Oilwell Cementing Co. LICENSE NUMBER _____

ADDRESS Conterbury Rd. Hays, Mo 67601

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 16 MONTH: 8 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Ted Crawford

(COMPANY NAME) Ohmer Oil Co. (PHONE) _____

WERE: Order 500 lbs. 50/50 permix - 6 7/8" tub.

PLUGGING PROPOSAL RECEIVED BY Galt G. Galt
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 16 MONTH: 8 YEAR: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 204' 5 1/2" set at 3370' w/ 125 lbs.

Top perf at 3222'. Ran 2" tubing to 3019' & spotted 65 lbs. cement to 1950'. Pulled tubing to 1844' & shot hole in casing @ 1950' then spotted 50 lbs cement to 1160'. Pulled tubing to 1000'; shot hole in casing @ 1160', spotted 40 lbs cement to 600'. Pulled tubing out & put on packer, ran in hole to 235' to test casing, REMARKS: pumped in 5 1/2" & out of 8 5/8". pulled tubing & packer. Pumped in 5 1/2" casing 345 lbs cement w/ 300 pounds pressure & cement to surface in 8 5/8"

I (DID / DID NOT) OBSERVE THIS PLUGGING.

RECEIVED SIGNED Galt G. Galt
STATE OF KANSAS CONSERVATION DIVISION (TECHNICIAN)

INVOICED
DATE 8-25-83
INV. NO. 5317-W

8-22-1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 6-83