

9-2

4-110026

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-22,558 - 00-00

SE SW SW /4 SEC. 29, 14 S, 18 W
330 feet from S section line
1650 feet from E section line

Operator license# 8640

Lease: Irvin Well # 1

Operator: Weilert Oil Company, Inc.

County: Ellis

Address: 866 230th Avenue
Hays, Kansas 67601

Well total depth 3722 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 1/2 inch @ 212 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: 332 W. Wichita, Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 2 Month: September Year: 1997

Plugging proposal received from: Michael Weilert

Company: Weilert Oil Company, Inc. Phone: 785-625-2888

Were: Ordered 170 sxs 60/40 pozmix - 10% gel and 12 sxs gel with 500# hulls
Plug thru casing. Tie onto backside, pressure up, pump cement and shut-in.

09-11-97

RECEIVED
MARRIOTT CORP
SEP 11 10 15 AM '97

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:45 A.M., Day: 2, Month: September, Year: 1997

Actual plugging report: 8 5/8" at 212' w/135 sxs. 4 1/2" at 3719' with 400 sxs cement. Tied onto 4 1/2" casing and pumped 50 sxs cement and 350# hulls, and then ran 14 sxs gel. Pumped 100 sxs cement and 150# hulls to Max. P.S.I. 800#. S.I.P. 300#. Tied onto backside and pumped 20 sxs cement and shut in at 600#. Total 170 sxs 60/40 pozmix - 10% gel - 500# hull - 14 sxs gel.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2050 GL

I did / did not observe the plugging.

Roger H. Moses
(agent)

Form CR-2/3

INVOICED

DATE 9-12-97

INV. NO. 48996

9-2 JAN 09 1998