

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23,204-0000

SW, Sec. 29, T 14 S, R 18 W/E

990 feet from S section line

900 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Irvin Well # 2

Operator: Oreiling Ltd.  
Name & Address 410 17th St.  
Suite 1140  
Denver Colo.

County Ellis

Well Total Depth 3723 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210 cwc 140sx

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number 5287

Address Hays Ks.

Company to plug at: Hour: 4:30 PM Day: 21 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Jim Montenger

(company name) C & R Dr. Inc. (phone) 913 628 3699

were: KB Elev. 2058 - Dak. map 1800 Anhydrite 1268-1311

Arbuckle-3678. Ordered 190 sx cem 50/50 por mix

6% gel, 3% cc. - pumped down drill stem. circ.

heavy mud. Spot 20 sx 3650 - 20 sx 1280 - 80 sx 660

40 sx 240 - 12 sx hulls, push plug to 40' & 105x on top.

105x Rat hole - 105x mouse hole. Signed Dale F. Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 PM Day: 21 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT The above well was plugged as follows

50/50 por mix 6% gel 3% c.c. pumped down drill pipe

20 sx @ 3650 - 20 sx @ 1280 - 80 sx @ 660

40 sx @ 240 - 12 sx hulls push plug to 40' pump

down 105x - 105x rat hole. - 105x mouse hole.

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1982

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-18-82

INV. NO. 1557-W

Signed Dale F. Balthazor  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82