

6060351

API NUMBER 15-051-22,630-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SESE SW, SEC. 24, T 14 S, R 18 W10
330 feet from N/S section line
2970 feet from A/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6717
Operator: Hankoff Oil & Gas
Name & Address: Petroleum Bldg. Suite 650
Denver, Co. 80202

Lease Name: J. Plannenstiel Well # 1
County: Ellis
Well Total Depth: 3770 122.53 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 1105'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling License Number 6050
Address: Box 176, Chase, Ks. 67524
Company to plug at: Hour: 9:00 AM Day: 12 Month: Oct. Year: 19 84

Plugging proposal received from Willard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457
were: Order 16.5 sh. 50% pozmix - 6 3/4" Gel - 3% cal. G., 20 sh. Gel., 5 sh. bulls
& 8 5/8" plug.

Plugging Proposal Received by Willard Kelso
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:00 AM Day: 12 Month: Oct. Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - 1105' w/ 450 sh. 4 1/2" at 3769' w/ 225 sh.
Top perf. at 3322'. Plugged bottom w/ castiron plug & 4 sh. cement
to 3200'. Shot pipe 2 times & recovered 2619'. Pumped in 8 5/8"
4 sh. bulls, 25 sh. cement, 15 sh. Gel., 70 sh. cement, 5 sh. Gel., 1 sh.
bulls, released plug & followed w/ 70 sh. cement w/ 750 pound. pressure.

Remarks: By Sun
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-29-84
INV. NO. 4507
10-12

RECEIVED
STATE CORPORATION COMMISSION
10-18-84
OCT 18 1984
CONSERVATION DIVISION
Wichita, Kansas

Signed Willard Kelso
(TECHNICIAN)

10-17-84
FORM CP-2/3
Rev. 01-84