

5-17

4-061081

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-22,609-00-00  
30'S. & 156' of  
SE SW SW /4 SEC. 24, 14 S, 18 W  
300 feet from S section line  
1824 feet from E section line

Operator license# 3321

Lease: K. Pfannenstiel Well # 1

Operator: Hoffman Petroleum, Inc.

County: Ellis 119.33

Address: 8 Glen Ridge Drive  
Littleton, CO 80123

Well total depth 3610 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1154 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Paramount Casing Crew License# 30970

Address: 2905 Barclay Drive, Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 17 Month: May Year: 1997

Plugging proposal received from: Ron Geist

Company: Paramount Casing Phone: 913-628-1099

Were: Order 250 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 3:00 P.M., Day: 17, Month: May, Year: 1997

Actual plugging report: 8 5/8" to 1154' w/450 sxs. 4 1/2" to 3608' w/150 sxs. Perfs at 3308' - 3312' - 3262' - 3268'. Sanded to 3200' and spotted 4 sxs cement with dump bailer. Cut casing loose at 2331' and pulled to 1815'. Mixed and pumped 85 sxs with 300# hulls. Pulled casing to 1200' and pumped 40 sxs cement with 200# hulls. Pulled casing to 525' and circulated cement with 70 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1950 GL

I did  / did not  observe the plugging.

DATE JUN 09 1997

INV. NO. 48290

5-17 JUL 22 1997

[Signature]  
(agent)  
Form CP-2/3

RECEIVED  
KANSAS CORP CO  
1997 JUN -4

06-04-97

INVOICED