

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 051-22838-00-00
SW, Sec. 24, T 14 S, R 18 W 18
2310 feet from ~~W~~/S section line
1320 feet from W/~~S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6216

Lease Name E. Leiker Well # 1

Operator: Edward P. Leiker
Name &
Address Manjor Rt. Hays, Mo. 67601

County Ellis

Well Total Depth 3570 feet 116.02

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1154'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Mo. 67524

Company to plug at: Hour: 10:00 AM Day: 13 Month: Jan Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs 50 gramic - 4 1/2 lbs. - 3 7/8 lbs., 20 lbs. gel, 5 lbs. pulls
+ 8 5/8" plug.

Signed Gilbert G. Leiker
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 PM Day: 13 Month: Jan Year: 1984

ACTUAL PLUGGING REPORT 8 5/8" - 1154' w/ 425 lbs cement, 4 1/2" at 3559' w/ 125 lbs cement

Top perf. at 3306'. Plugged bottom w/ 4 lbs cement, sand & 4 lbs cement
to 3400'. Shot pipe 1 string & recovered 2804'. Pumped in 8 5/8" - 4 lbs pulls,
25 lbs cement, 15 lbs. Gel, 70 lbs cement, 5 lbs. Gel, 1 lb. pulls, released plug & followed
w/ 70 lbs cement w/ 1000 pounds pressure

Remarks: By Allied Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION

Signed Gilbert G. Leiker
(TECHNICIAN)

DATE 1-26-84 JAN 23 1984

FORM CP-2/3 Rev. 9-82 15

INV. NO. 9264-64 CONSERVATION DIVISION Wichita, Kansas