

6 020335

API NUMBER 15-051-24-419-00-06

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N 05 W 34 SEC. 22, T 14 S, R 18 W 1/2

990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Gross Well # 1

Operator: Damar Resources Inc

County Ellis, 118.14

Name & Address: Box 70

Well Total Depth 3635 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Kon. Drilg. License Number 4038

Address Hays, Ks. 67601

Company to plug at: Hour: 12:00 Day: 18 Month: Aug. Year: 19 86

Plugging proposal received from Frank Taggert

(company name) Air Heavy Mud + Pump Down (phone) 913-625,0020

were: Drill Stem, 25 sx @ 3500, 25. sx @ 1290,

80 sx @ 620, 40. sx @ 270, 10 sx @ 40' + 15. sx R.H.,

K.B.: 2005 map, 1750 only 1217- to 1258 Arb. @ 3600

60/40 Poz 4% Gel. 3% cc w/ 1.9x Cel. Flake

Plugging Proposal Received by

Julius Palkozer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:30 A Day: 18 Month: Aug. Year: 19 86

ACTUAL PLUGGING REPORT Pumped Down Drill Stem, 25 sx @

3562, 25 sx @ 1260, 80 sx @ 620, 40. sx @ 270

10. sx @ 40 + 15 sx in Rat Hole.

60/40 Poz, 4% Gel. 3% cc w/ 1.9x F.10. Cel.

Remarks: By Allied. LIVED

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 22 1986

INV. NO. 14802

08-22-86
AUG 22 1986

Signed *Julius Palkozer*
(TECHNICIAN)

8-22-86

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 8 05 86 month day year

API Number 15-051-24,419-00-00

OPERATOR: License # 9067 Name DaMar Resources, Inc. Address P.O. Box 70 City/State/Zip Hays, KS 67601 Contact Person Daniel F. Schippers Phone (913) 625-0020

NW/4 SW/4 SW/4 Sec. 22 Twp. 14 S, Rg. 18 East X West 990 Ft. from South Line of Section 4950 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # Name Unknown City/State

Nearest lease or unit boundary line 330 feet County Ellis Lease Name Gross Well # 1

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation 2005 est. feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 60 Depth to bottom of usable water 500 600 Surface pipe planned to be set 200 Projected Total Depth 3670 feet Formation Lansing-Arbuckle

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 7-16-86 Signature of Operator or Agent Title President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. This Authorization Expires 1-17-87 Approved By 7-17-86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (e.g., 3600, 1225, 550, 300, 40, 10), feet depth with, and sxs of (e.g., 60/40 poz, 6% gel). Includes note for (b) Mousehole with sxs.

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. Important: Call district office after well is either plugged or production casing is cemented in (Call 7 a.m. to 5 p.m. workdays)

District office use only: API #15-051-24,419 Surface casing of feet set with Alternate 1 or 2 surface pipe was used. Alternate 2 cementing was completed @ ft. depth with Hole plugged 19 agent

RECEIVED KCC-KDHE JUL 21 1986 JOINT-DIST #6 HAYS, KS

Set. 265' 8 5/8" 140 sha. 50/50 poz. 2 7/8" Allied Cementing 3% C.C. cur 6:00 AM 8/12/86 Hays, KS API 15-051-24,419