

4-041344

12-17

213
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-23,847-00-00

NE NE NE /4 SEC. 20, 14 S, 18 W
4950 feet from S section line
330 feet from E section line

Operator license# 8061 Lease Leonhardt well # 1

Operator: Oil Producers, Inc. of Ks. County Ellis

Address: P.O. Box 8647 Well total depth 3651 feet ^{118.65}
Wichita, Kansas 67208 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 215 feet
w/125 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: Day: 17 Month: December Year: 91

Plugging proposal received from: Brad Siroky

Company: Oil Producers, Inc. of Kansas Phone:

Were: 4 1/2" casing set @ 3651' w/125 sx. Perfs. @ 3377' - 79' and
3405' - 13'. Squeezed @ 1255' w/300 sx. circ. Ordered 300 sx. 60/40
pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:55A.M., Day: 17, Month: December, Year: 91

Actual plugging report: W.P.M. to 3600'. Hooked-up to 8 5/8"
S.P. Pumped in 155 sx. cement. P.S.I. Max. 600#. S.I. 600#.
Hooked-up to 4 1/2" casing. Pumped in 25 sx. cement followed w/260 sx.
cement w/400# hulls mixed in cement. Max. P.S.I. 600#. S.I. 400#.

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1991
12-26-91

Remarks:

I did[X] / did not [] observe the plugging.

Dennis L. Hamel

DATE 1-10-92

INV. NO. 34304

12-17 MAR 17 1992

(agent)

Form CP-2/3