

8-16

6-100416

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-24,676 00-00

S2 NW /4 SEC. 20, 14 S, 18 W  
330 feet from S section line  
3160 feet from E section line

Operator license# 3919 Lease Rohr well # 1

Operator: Challenger Exploration County Ellis

Address: P.O. Box 1112 Well total depth 3710 feet - 120.57  
Hays, Kansas 67601 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 485 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Tri-United, Inc. License# 3194

Address: Hays, Kansas 67601

Company to plug at: Hour: ?? Day:     Month:     Year:    

Plugging proposal received from: Edward Leiker

Company: Tri-United, Inc. phone:    

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 3167 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1280 feet " 25 " Mousehole:     sacks

3rd plug @ 610 feet " 140 "

4th plug @ 40 feet " wiper plug & 10 sx

5th plug @     feet

Plugging Proposal Received by:      
Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

RECEIVED  
STATE CORPORATION COMMISSION  
08-22-90  
AUG 22 1990

CONSERVATION DIVISION  
Wichita, Kansas

Completed: Hour: 1:00 am, Day: 16, Month: August, Year: 1990

Actual plugging report: Hole reported plugged as above.  
Order 215sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2060 GL, Anhydrite depth: 1280 - 1327 feet

Did     penetrate Arbuckle, cemented by Halliburton

I did[     ] / did not[ X ] observe the plugging.    

INVOICED

DATE: 8-29-90

INV. NO. 29150  
8-16

*J.S.*

David K. Wann P.I.R.T. II  
(agent)