

6 030874

5-15-87

API NUMBER 15- 051-01,002-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW ^{SE} ~~NE~~ NW, SEC. 20, T 14 S, R 18 ^{W/E}
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9121
Operator: Kiwanda Res. Inc.
Name & Address: P.O. Box 1320
Wichita, Ks. 67202

Lease Name Rohr Well # 1
County Ellis 120.71
Well Total Depth 3714 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 175'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address Ness City, Kansas

Company to plug at: Hour: AM Day: 15 Month: 5 Year: 1987

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) _____

were: Order 150 sx 65/35 poz 10% gel 2% Dical Thriftymix. and 5 sk hulls.

B.J. Tittan Cmt. Co.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 15 Month: 5 Year: 1987

ACTUAL PLUGGING REPORT 8 5/8" set at 175' with 130 sks 4 1/2" set at 3713' with 175 sks

Perforated pipe at 650', 50' below base of Dakota. For block squeeze. Mix and pump down 4 1/2" 135 sx cmt mix with 4 sk hulls max PSI 100# close in at 100 # mix and pump down annulus 15 sx cmt mix 1 sx hulls locked up closed in at 300 # PSI.

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-87

INV. NO. 12353

Signed *Carl Goodrow*
Carl Goodrow (TECHNICIAN)

DB