

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23537-0000

NW SEC. 19, T. 14S., R. 18W/E R

2300 FEET FROM N/4 SECTION LINE

2300 FEET FROM W/4 SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6691

LEASE NAME Johnson WELL # 2-19

OPERATOR: Terramax Energy Inc

COUNTY Ellis

NAME & ADDRESS Box 484

WELL TOTAL DEPTH 3760 \$122.20 FEET

monument Colo.  
80132

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 8 5/8 FEET 333

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL (D&A)

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR circle m Drilg. Co. LICENSE NUMBER 6591

ADDRESS Box 128 Oberlin Ks. 67749

COMPANY TO PLUG AT: HOUR: 2 PM DAY: 23 MONTH: 7 YEAR: 1983

PLUGGING PROPOSAL RECIEVED FROM Larry Taylor 475-3833

(COMPANY NAME) circle m Drilg co. 913 (PHONE) 625-2563

WERE: Order 170 sx. cement 50/50 pozmix 6% Gel. 3% cal. cl.

1sx. hulls 1-8 5/8 plug.

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 2103 Anhydrite 1328-50 Arbuckle 3750

Dakota 1750 PLUGGING PROPOSAL RECEIVED BY Pale Z. Balthazor  
353 = 650 (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE (circled)

OPERATIONS COMPLETED: HOUR: 10:30<sup>PM</sup> DAY: 23 MONTH: 7 YEAR: 1983

ACTUAL PLUGGING REPORT Circulate on bottom 15 mi.

1st. plug 25 sx. @ 3750

2nd. plug 25 sx. @ 1340

3rd. plug 100 sx. @ 650 1sx hulls push plug 40'

4th plug 10 sx @ 40

10 rat hole.

REMARKS: Farmers Irrigation well @ 440'

cementing Co.

I (DID (DID NOT)) OBSERVE THIS PLUGGING.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

SIGNED

Pale Z. Balthazor  
(TECHNICIAN)

DATE

8-11-83

AUG 08 1983

INV. NO.

5114-W

08-08-83  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
REV. 6-83