

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-063-20,719-00-00

LEASE NAME Albin

WELL NUMBER #1

4620 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 22 TWP. 14 RGE. 27 (W)

COUNTY Gove

Date Well Completed 1-10-84

Plugging Commenced 8-26-87

Plugging Completed 8-28-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS 211 N. Robinson, Suite 1700, OKC, Okla. 73102

PHONE# (405) 239-7031 OPERATORS LICENSE NO. 6593

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #4, Carl Goodrow

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4334' Bottom 4341' T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	oil	4334 -	41'	8-5/8"	330	---
				4-1/2"	4400	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

POOH w/rods & pump. Pump 5 sxs CSH & 150 sxs Econolite cmt. Pump 25 sxs Econolite down 8-5/8" X 4-1/2" annulus. Cutoff 8-5/8" and 4-1/2" csg. 3' BGL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Howco License No. _____

Address Hays, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss. OCT 6 1987

C. Brad Crouch (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Brad Crouch

(Address) 211 N. Robinson, Suite 1700, OKC, OK 73102

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 87

Diana Thompson Notary Public

My Commission Expires: Nov. 18, 1988

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA, KANSAS

15-063-20719-00-00



GAMMA-CORRELATION MICRO-SEISMOGRAM CASED HOLE LOG

COMPANY WELL FIELD County State	COMPANY <u>CINCO ENERGY COMPANY</u>
	WELL <u>#1 ALBIN</u>
	FIELD <u>WILDCAT</u>
	COUNTY <u>GOVE</u> STATE <u>KANSAS</u>
	Location <u>590 FNL</u> <u>970 FEL</u> <u>C 1/2 NE NE</u>
Sec. <u>22</u> Twp <u>14^s</u> Rge <u>27^w</u>	

Permanent Datum <u>GROUND LEVEL</u>	Elev. <u>-2483</u>	Elev.: K.B. <u>2488</u>
Log Measured From <u>S.A.G.L.</u>	Ft. Above Perm. Datum	D.F.
Drilling Measured From <u>KELLY BUSHING</u>		G.L. <u>2483</u>

Run No.	<u>ONE</u>	
Date & Time Survey	<u>1-27-84 4:00 PM</u>	
Date & Time Cementing	<u>1-10-84 2:17 PM</u>	
Type Cementing Operation	<u>2 STAGE</u>	
Depth Driller	<u>4400</u>	
Depth Welex	<u>4364</u>	
Logged Interval	<u>4358</u>	to <u>2250</u>
Casing Driller	<u>8 5/8</u>	@ <u>300</u>
Float Collar—D.V. Tool	<u>2313</u>	
Squeeze Depth	<u>N.A.</u>	
Amount & Type Cement	<u>150 SKS CLASS A</u>	<u>475 SKS HOWCO LITE</u>
Amount & Type Admix	<u>10% SALT, 3 1/2% CERZ, 1/4% SK FLOCEL</u>	<u>7% SK GILSONITE, 1/4% SK FLOCEL</u>
Type Fluid in Hole	<u>WATER</u>	
Fluid Level	<u>FULL</u>	
Salinity PPM Cl	<u>N.A.</u>	
Weight lb/gal—Vis.	<u>N.A.</u>	
Approx. Logged Cem. Top	<u>3400'</u>	<u>BOTTOM STAGE</u>
Calculated Cement Top	<u>N.A.</u>	
Max. Hole Temperature	<u>110°</u>	°F.
Tool No.	<u>307</u>	<u>* 23950</u>
Spacing Recorded	<u>4'</u>	
Equipment—Location	<u>1914</u>	<u>COLBY</u>
Recorded by	<u>B. HOCKERT</u>	
Witnessed by	<u>MR. STEEN</u>	